



REQUEST FOR QUOTE

March 27, 2023

Please provide quote to remove and install 2 sets of existing masonry steps consisting of 3 risers (approx. 7" h) and 3 treads (approx. 11" h) on the Washington Park gazebo structure. New steps to match how existing steps currently are esthetically designed, but installed in concrete, unlike the currently existing steps that are a combo of brick and concrete. Current railings planned to be reused, but please provide an additional cost estimate for new stair railings in case the old railings cannot be used. Please itemize quote by demo, install, and new railing.

Quotes Due by 10:00 AM, April 6, 2023

Send Quote to:

Vince DeJoy, Director
Department of Planning & Development
342 Central Ave.
Dunkirk, NY 14048
vdejoy@cityofdunkirk.com

Specifications:

INSTALL 2 SETS OF CONCRETE STAIRS ON WASHINTON PARK GAZEBO

- 1 Removal and disposal of both steps on north and south of structure.
- 2 Remove and save existing stair railing.
- 3 Install new cast in place for concrete steps.
- 4 Steps are approximately 6ft wide and 2.5ft tall in height.
- 5 Re-install existing stair railing (if need be install new stair railing).
- 6 Davis-Bacon regulations apply.
- 7 NYS wage determination be included in quote proposal.
- 8 HUD Form 4010 and HUD Form 5370 regulations apply.
- 9 A City permit application will be required; however, the fee will be waved.

Current Conditions at Washington Park Gazebo

